

Getting Started with the
Lightcloud Installation App

LC Installer

Overview

Features

Installation Steps

Overview

Use the Installer App to scan and organize Lightcloud Devices. The Device information is then seamlessly sent to RAB for free, remote commissioning. It's really that simple.


Features

- Multi-Site
- Multi-Gateway
- Assign Devices to Rooms
- Assign Device Zone Names
- Assign Dimmers to Controllers
- Create Installation Notes

The Installer App is for setting up/commissioning a Lightcloud system. For lighting controls and management, please use the Lightcloud App.

Questions?

1 (844) - LIGHTCLOUD




Follow these easy steps to install your Lightcloud site.

1. Position the Gateway

The Gateway should be located centrally to as many Lightcloud devices as possible and have a strong cellular signal.


Test the Gateway Signal Strength—must be green before installation.



Install one Gateway and related devices at a time.

2. Scan the Gateway's Device ID

The Device ID is used to identify each device in the system.




Device IDs



3. Permanent Power to the Gateway


Wire the Gateway for permanent, unswitched power.



Don't use a plug-in power cord for permanent installation.

4. Position Devices

Lightcloud devices send, receive, and repeat wireless signals. Each device needs to be within range of at least one other device and have a pathway back to the Gateway.




4. Position Devices Continued

Indoor Range: 100 feet through standard building materials such as drywall.

Outdoor Range: 1000 feet without any obstructions.

Use the chart below to see affects of various building materials.



5. Scan Device


Scan Device ID and verify that the number scanned correctly.

Device IDs




6. Complete Device Information

Be as detailed as possible.




7. Install Devices

Wire for permanent, unswitched power.




8. Test Devices

Ensure the status indicator is solid Green and test dimming and switching using the device identification button.



9. Send to RAB

After scanning and installing all of the devices, submit the information by pressing 'Send to RAB'.



More Info

View the Planning Guidelines

Visit lightcloud.com/resources

Questions?

Free Support — Call 1(844)LIGHTCLOUD

Interested?

lightcloud.com

1 (844) LIGHTCLOUD